

BRUHAT BANGALORE MAHANAGARA PALIKE**DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

**Name of Work: Repairs & Maintanance of Borewells at Sidedahalli Village Limit
Ward No 14 Bagalagunte**

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts	Mtrs	950.00	151.00	Rupees One hundred Fifty one only
2	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specifcation	Nos	5.00	1530.00	Rupees One thousand Five hundred thirty Only
3	Supplying and fixing 50mm GM Gae Vavle	Nos	5.00	1430.00	Rupees One thousand Four hundred thirty Only
4	Supplying and fixing 160mm Borewell cap with clampset	Nos	5.00	690.00	Rupees Six hundred Ninty Only
5	Supplying and fixing 50mm GI Union	Nos	5.00	245.00	Rupees Two hundred forty five only
6	Supplying and fixing 50mm GI Elbow	Nos	20.00	120.00	Rupees One hundred Twenty Only
7	Supplying and fixing 50mm GI coller Heavy duty	Nos	20.00	1350.00	Rupees One thousand Three hundred fifty Only
8	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp	Nos	8.00	10000.00	Rupees Ten thousand only
9	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset	Mtrs	288.00	402.75	Rupees Four hundred two & Seventy Five Paise only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

24

10	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., complete	Nos	8.00	475.00	Rupees Fou hundred Seventy five only
11	Supplying and fixing 500x500x65mm polished wood board made up not less than 15mm thick plank in front plank one end provided for olding at other end fixing the same of the valve using through bolts and nuts,	Nos	8.00	275.00	Rupees two hundred Seventy five only
12	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity	Nos	8.00	350.00	Rupees Three hundred fifty Only
13	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required	Nos	8.00	1075.00	Rupees One thousand Seventy Five only
14	Supply 1.1 KV class UG cable from nearest BESCOM pole to panel board including earth work and road restoratio 4 core 16 sqmm	Mtrs	100.00	150.00	Rupees One hundred fifty Only
15	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required	Mtrs	100.00	5.00	Rupees Five only
16	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc.	Mtrs	75.00	50.00	Rupees Fifty only
17	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc.,	Nos	50.00	219.00	Rupees Two hundred Nineteen Only
18	Transportation of pumping machineries		8.00	850.00	Rupees Eight hundred fifty only
19	Erection of Pumping machineries		8.00	850.00	Rupees Eight hundred fifty only




EXECUTIVE ENGINEER-4
KRIIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer